



Project RoU Verification Report

  2026

COVER PAGE	
RoU Project Verification Report Form (VR)	
BASIC INFORMATION	
Name of approved UWR Project Verifier / Reference No.	INI Infrastructure & Engineering Private Limited
Type of Accreditation	☒ RoU Accreditation UWR ☐ Water Audit/Water Footprint Expertise
Approved UWR RoU Scopes for Project Verification	Scope 4: measures that remove bacteriological and other impurities from seawater*, sewage/wastewater contaminated water bodies or other contaminated water bodies, so that water is made suitable/fit for re-use and recycling purposes. The water bodies are outside the project's fence boundary. Scope 5: conservation measures taken to recycle and reuse water, spent wash, wastewater etc across or within specific industrial processes and systems.
Validity of UWR approval of Verifier	20/02/2024 Onwards
Completion date of this VR	21/08/2026
Title of the project activity	Gainful use of sewage wastewater industrial effluent at Ankur Textiles Ltd
Project reference no. (as provided by UWR RoU Program under Approved for Verification tab)	UWR ID No. 578
Name of Entity requesting verification service (Can be Project Owners themselves or any Entity having authorization of Project Owners, example aggregator.)	Arvind Envisol Limited
Contact details of the representative of the Entity, requesting verification service	Mr. Kunal Barad Contact Detail: +91 9574846476 Email ID: kunal.barad@arvind.in
Country where project is located	INDIA



Applied reference documents used for estimation (approved water data and reference guides under the UWR RoU Standard used)	• PCNMR • UWR Verification Standard Version 8 • UWR Verification Templet 2022 • UWR Terms and Conditions • National Building Code of India 2016
Project Verification Criteria: Mandatory requirements to be assessed	☒ UWR Standard ☒ Applicable Approved Calculations ☒ Applicable Legal requirements /rules of host country ☒ Eligibility of the Project Type ☒ Start date of the Project activity ☐ Meet applicability conditions in the applied methodology ☐ Credible Water Data Sets ☒ Do No Harm Test ☒ RoU calculations ☒ PCNMR ☒ No Double Counting ☒ Others (please mention below) ☒ Physical Site Visit and Observation ☒ Legal Aspects
Project Verification Criteria: Optional requirements to be assessed	☒ Environmental Safeguards Standard and do-no-harm criteria ☒ Social Safeguards Standard do-no-harm criteria ☒ AMC Chalan for STP Water ☒ Agreement between Arvind and Ankur for O&M of 1.75 MLD ETP ZLD Plant ☒ NoC ☐ ETP Commissioning Report ☒ Supporting Occupancy data
Project Verifier's Confirmation: The <i>UWR Project Verifier</i> has verified the UWR project activity and therefore confirms the following:	The UWR RoU Project Verifier INI Infrastructure & Engineering Private Limited, certifies the following with respect to the UWR Project Activity Gainful use of sewage wastewater industrial effluent at Ankur Textiles Ltd. ☒ The Project Owner has correctly described the Project Activity in the PCNMR (dated August 2026) including the applicability of the guidance



	documents and water data as outlined in the UWR RoU Standard. RoU Scope 4: measures that remove bacteriological and other impurities from seawater*, sewage/wastewater contaminated water bodies or other contaminated water bodies, so that water is made suitable/fit for re-use and recycling purposes. The water bodies are outside the project's fenced boundary. RoU Scope 5: conservation measures taken to recycle and reuse water, spentwash, wastewater etc across or within specific industrial processes and systems. During the course of verification, the Verifier identified that the RoU calculations presented in Table 11.1 of the PCNMR were not fully reconciling with the underlying water reuse quantities presented in Tables 10.2, 10.3 and 10.4. Specifically, discrepancies were identified in the Scope 5 calculations relating to ETP-treated water reuse and RO permeate reuse for the applicable vintage years. Accordingly, CAR-01 was raised by the Verifier. In response to the CAR, the Project Proponent revised the relevant RoU calculations and updated the PCNMR. The Verifier reviewed the revised Tables 10.2, 10.3, 10.4 and 11.1, together with the supporting documents and records submitted by the Project Proponent, and confirmed that the year-wise RoU calculations and the corresponding Scope 4 and Scope 5 quantities have been reconciled. The revised PCNMR reports a total gross RoU quantity of 43,76,859 m³ for the verification period from 01/01/2015 to 31/12/2025. The Verifier further reviewed the application of the 2% conservative uncertainty deduction to the respective vintage-year RoU quantities in accordance with the applicable UWR RoU requirements. The revised PCNMR incorporates the prescribed uncertainty deduction in the year-wise RoU calculations, resulting in a final eligible RoU quantity of 42,89,322 m³, as reported in the revised
--	---

	PCNMR. The Verifier further confirmed that the treated sewage wastewater sourced from Ahmedabad Municipal Corporation (AMC) and utilised by the Project Proponent prior to commissioning of the ETP system is supported by satisfactory documentary evidence and corresponding records submitted during verification. Although the ETP commissioning report was not available with the Project Proponent, the operational status and functionality of the ETP system were physically verified during the site inspection, and the available inlet-outlet monitoring data and supporting operational records used for RoU calculations were found acceptable for verification purposes. Further, it was brought to the attention of the Verifier during the verification process that the Water Credits (RoUs) generated through the present Project Activity are proposed to be availed by Arvind Envisol Limited. The same has been duly acknowledged and consented to by Ankur Textiles Ltd., and the Verifier has confirmed such authorization based on the No Objection Certificate (NOC) and CA Certificate submitted during the verification process. ☒ The Project Activity is assessed to be eligible for 42,89,322 m³ of RoUs, subject to incorporation of the revised year-wise RoU calculations, including the applicable 2% conservative uncertainty deduction, in the revised PCNMR. ☒ The Project Activity is not likely to cause any net-harm to the environment and/or society ☒ The Project Activity complies with all the applicable UWR rules¹ and therefore recommends UWR Program to register the Project activity with RoUs. In response to the CAR, the Project Proponent revised the relevant RoU calculations. The Verifier reviewed the revised calculations and confirms that
--	---

	the Project Activity complies with the applicable UWR requirements for RoU Scope 4 and Scope 5. Based on the verification performed, the Project Activity is eligible for 42,89,322 m ³ of RoUs
Project Verification Report, reference number and date of approval	
Name of the authorised personnel of UWR Project Verifier and his/her signature with date	 Mr. Chintan Thanki Associate Director – Legal / Finance

PROJECT VERIFICATION REPORT

Executive summary

Ankur Textiles Limited has appointed INI Infrastructure & Engineering Private Limited as verifier to carry out the verification of the project activity "Gainful use of sewage wastewater and industrial effluent at Ankur Textiles Limited" under UWR RoU Scope 4 and Scope 5. This refers to verification of Rainwater Offset Units (RoUs)/Water Credits generated over the monitoring and verification period from 01/01/2015 to 31/12/2025. The project activity aims to conserve freshwater and groundwater resources through gainful reuse of treated sewage wastewater, industrial effluent, treated water from ETP/STP systems and RO permeate water within the textile manufacturing operations while promoting sustainable water management practices as a Zero Liquid Discharge (ZLD) unit.

The verification process included review of the Project Concept Note and Monitoring Report (PCNMR), supporting calculations, monitoring records, water balance data and applicable UWR standards and methodologies. The verification was carried out through physical site visit, off-site document review, virtual interactions and submission of supporting documents through emails as per UWR standards. Physical site inspection was conducted on 03/04/2026 wherein ETP, STP, RO systems, pipelines and meter readings were inspected and verified.

During the verification, discrepancies were identified in the RoU calculations presented in the PCNMR, particularly with respect to the reconciliation of the calculations under Tables 10.2, 10.3, 10.4 and 11.1. Accordingly, corrective actions were raised by the Verifier, following which the Project Proponent revised the relevant RoU calculations in the PCNMR. The revised PCNMR was reviewed by the Verifier and the year-wise RoU calculations were found to be reconciled. The applicable 2% conservative uncertainty deduction was also incorporated in the revised RoU calculations in accordance with the applicable UWR requirements. Based on the revised calculations and verification performed, INI Infrastructure & Engineering Private Limited has assessed the Water Credits (RoUs) generated from the Project Activity for the period from 01/01/2015 to 31/12/2025 at 42,89,322 m³.

Project Verification team, technical reviewer and approver

Project Verification team

No.	Role	Last name	First name	Affiliation	Involvement in		
					Doc review	Off-Site inspection	Interviews
1.	Team Leader Validator	Thanki	Chintan	N/A	YES	YES	YES
2.	Technical Expert	Thakkar	Nehal	N/A	YES	YES	YES
3	Technical Expert	Vadukul	Vishal	N/A	YES	YES	YES
4	Legal Verifier	Vellotuparambil	Anjali	N/A	YES	YES	NO

Technical reviewer and approver of the Project Verification report

No.	Role	Type of resource	Last name	First name	Affiliation
1.	Technical reviewer & Approver	PCNMR and other Documents	Thakkar	Nehal	INI INFRASTRUCTURE & ENGINEERING PRIVATE LIMITED



2.	Technical reviewer	PCNMR and other Documents	Vadukul	Vishal	INI INFRASTRUCTURE & ENGINEERING PRIVATE LIMITED
3.	Approver	PCNMR and Other Documents	Thanki	Chintan	INI INFRASTRUCTURE & ENGINEERING PRIVATE LIMITED

Means of Project Verification

Desk/document review

As part of the review and verification process, Ankur Textiles Limited submitted a Project Concept Note and Monitoring Report (PCNMR), water credit calculation Sheet, Photographs, AMC acknowledgment and other relevant data were provided upon request pertaining to this project examination to the Lead and Technical Verifier. These documents are thoroughly reviewed to ensure compliance with the UWR standards and to validate the completeness of the information and data provided.

On Site and Off-site inspection

Date of on site inspection: 03/04/2026			
No.	Activity performed On-Site	Site location	Date
1.	Visited the Site	Ahmedabad, Gujarat	03/04/2026
2.	Supporting documents provided before, during and after the visit for verification and confirmation	Ahmedabad, Gujarat	February 2026 till 27/07/2026

Interviews

No.	Interview			Date	Subject
	Last name	First name	Affiliation		
1.	Panchal	Pravin	Ankur Textile Limited	03/04/2026	Project Activity at Site
2.	Shah	Vivek	Project Aggregator and Consultant	03/04/2026	Project Activity and RCNMR
3.	Barad	Kunal	Ankur Textile Limited	02/07/2026	Project Activity, Documentation and Other required details for verification

Clarification request (CLs), corrective action request (CARs) and forward action request (FARs) raised

Areas of Project Verification findings	No. of CL	No. of CAR	No. of FAR
Rainwater Offset Units or Water Credits (RoU)			
Identification and Eligibility of project type	Nil	Nil	Nil
General description of project activity	Nil	Nil	Nil
Application and selection of methodologies and standardized sets	-	-	-
- Application of RoU methodologies and standardized data sets	3	Nil	Nil
- Deviation from methodology and/or methodological tool	Nil	Nil	Nil
- Clarification on applicability of methodology, tool and/or standardized data sets	1	Nil	2
- Project boundary and unutilized water sources	Nil	Nil	Nil

- Likely scenario without RoU Project	Nil	Nil	Nil
- Estimation of RoUs	Nil	1	Nil
- PCNMR	1	Nil	Nil
Start date, crediting period and duration	1	Nil	Nil
Positive environmental impacts on water table and/or groundwater recharge and/or water security in the area	Nil	Nil	Nil
Project Owner- Identification and communication	1	Nil	Nil
Others (please specify)	Nil	Nil	Nil
Total	7	1	2

Section D. Project Verification Findings

Identification and eligibility of project type (Approved Project Activities (Positive List))

Means of Project Verification	For identification and eligibility of the project type below mentioned data were referred and verified: - Project Document: detailed project Reports, including the PCNMR, outlining of the project's scope and outcome, the AMC letters, - On Site & Off Site inspection: On Site to verify that Implementation and Operation of the Project activity y, including physical inspection of the STP, ETP and RO systems, review of operational records, calculation sheets, monitoring data, and supporting documents submitted by the Project Proponent.
Findings	CL-01 was raised regarding supporting records and applicability of AMC treated sewage water utilized by the Project Proponent prior to commissioning of the ETP system. CL-02 and CL-03 were raised regarding applicability and adequacy of operational and monitoring data used for estimation of RoUs under Scope 4 and Scope 5.
Conclusion	Based on the documents reviewed, site verification conducted, and clarifications submitted by the Project Proponent, the Verifier confirms that the Project Activity is eligible under RoU Scope 4 and Scope 5 and complies with the applicable requirements of the UWR RoU Standard.

D.2 General description of project activity

Means of Project Verification	Below were reviewed for UWR project activities description verification: - Project Documentation: detailed project reports, including the Project Concept Note & Monitoring Report (PCNMR), outlining the projects scope, objectives, and outcomes. - Onsite & Off-Site inspection to verify the implementation and operation of the project activities. - Supporting Data: - STP inlet and outlet audit reports of the relevant year. - Environmental Audit Reports - Working days and Employee count provided by the Project proponent - Document from AMC for sewage reuse - Flow meter Calculation Certificate - ETP and RO operational monitoring records
Findings	Upon verification, it was observed that the Project Activities



	described in the PCNMR are physically implemented and operational at site, and the treatment/reuse systems are functioning in line with the project description submitted by the Project Proponent. The STP, ETP, and RO systems were found operational during the site visit, and the reuse mechanism/process adopted by the PP was found consistent with the Project Activity description provided in the PCNMR. CL-02, CL-03, CL-04, and CL-05 were raised regarding ETP commissioning details, operational data basis, maintenance records, flow meter calibration, and inlet-outlet monitoring parameters utilized for RoU calculations. The responses and supporting documents submitted by the Project Proponent were reviewed and found satisfactory for verification purposes. However, the ETP commissioning report was not available with the Project Proponent. The operational status and functionality of the ETP were nevertheless verified through site inspection and the available operational and supporting records.
Conclusion	Based on the documents reviewed, site verification conducted, and clarifications submitted by the Project Proponent, the Verifier confirms that the general description of the Project Activity provided in the PCNMR is consistent with the actual implementation and operation observed during verification. Although the ETP commissioning report was not available, the operational status and functionality of the ETP system were verified through site inspection and supporting operational records.

D.3 Application and selection of water data and calculation parameters

Means of Project Verification	PCNMR, operational monitoring records, AMC sewage inlet data, ETP/RO outlet data, and flow meter readings were reviewed for verification of application and selection of water data and calculation parameters. Calibration certificates and AMC-related water intake records were also verified. On-site inspection was also conducted to verify system operations and data reliability.
Findings	CL-05 was raised with respect to AMC sewage inlet records and calibration of water meters used for data measurement. The water data and calculation parameters used for RoU estimation were verified against supporting operational records and found generally consistent with the monitoring system in place. However, minor reconciliation was required in the RoU calculation tables, which was addressed under CAR-01.
Conclusion	The water data sources and calculation parameters applied in the PCNMR were found acceptable for verification purposes. CAR-01 was subsequently closed upon satisfactory review of the revised calculations.

D.4 Project boundary, sources and RoUs

Means of Project Verification	The Project boundary was ascertained based on the information provided in the PCNMR, including the satellite image depicting the project site.
Findings	CL-07 was raised to obtain clarification and supporting evidence regarding the ownership of the Project Site, including the land, plant and machinery associated with the Project Activity.
Conclusion	Project Boundary has been considered by the image shown in PCNMR report however the ownership of the project site and

	plant and machinery have been clarified by obtaining a CA certificate in this regard accordingly CL-07 stands closed.
--	---

D.4 Baseline scenario of the water shed or activity prior to project commissioning

Means of Project Verification	N/A
Findings	N/A
Conclusion	N/A

D.5 Implementation Benefits to Water Security

Means of Project Verification	AMC records, ETP operational records, RO treatment records, Environment Report and supporting documents submitted by the Project Proponent were reviewed. • Site inspection was conducted to verify reuse and recycling systems implemented under the Project Activity.
Findings	CL-03 and CL-05 were raised regarding inlet-outlet monitoring data and AMC sewage inlet records utilized for reuse calculations under the Project Activity. The clarifications and supporting records submitted by the Project Proponent were reviewed and found satisfactory for verification purposes. The STP, ETP, and RO systems were found operational, and the treated water generated from the systems is being reused for industrial purposes.
Conclusion	The Project Activity results in reduction of freshwater consumption through reuse and recycling of treated wastewater and RO treated water, thereby contributing towards water conservation and improvement in water security.

D.6 Clarification on applicability of tool and/or RoU estimates

Means of Project Verification	- PCNMR, operational records, inlet-outlet monitoring data, and supporting documents submitted by the Project Proponent were reviewed. - On-site inspection was conducted to verify applicability of the methodology, operational status of STP/ETP/RO systems, and basis of RoU estimates.
Findings	FAR-01 was raised regarding maintenance and availability of supporting commissioning and operational records for future verification periods. Although the ETP commissioning report was not available, the operational status and functioning of the ETP were verified through the available operational records and physical site inspection, which were found satisfactory for verification purposes.
Conclusion	Based on the documents reviewed, site inspection conducted, and verification of operational records, the applied methodology and RoU estimation approach were found to be acceptable and in line with the applicable UWR RoU Standard.



D.7 Estimation of RoUs or net water saved/recycled/reused

Means of Project Verification	Below were assessed to verify calculation of RoUs: For Scope 4 & 5: • The AMC certificate was checked to collect data for AMC sewage reuse • Occupancy data collected for STP calculation • ETP commence and operational records • Meter readings provided inlet and outlet
Findings	Upon verification of the PCNMR and site inspection, CL-01, CL-03, CL-04, CL-05, and CL-06 were raised to verify the operational basis, inlet-outlet parameters, AMC sewage data, ETP operational records, and water meter readings considered for RoU estimation. Further, CAR-01 was raised as the RoU calculations presented in Table 11.1 were not fully consistent with the source data provided in Tables 10.2, 10.3 and 10.4 of the PCNMR. The Project Proponent subsequently submitted an updated PCNMR incorporating the revised RoU calculations. Based on the revised calculations, the gross RoU quantity was revised from 43,22,486 m³ to 43,76,859 m³. The applicable 2% conservative uncertainty deduction of 87,537 m³ was thereafter applied to the total RoU quantity in accordance with the applicable UWR RoU requirements. Accordingly, the final eligible RoU quantity was determined as 42,89,322 m³. CAR-01 was subsequently closed upon satisfactory review of the revised calculations. FAR-02 was raised to recommend that, for future monitoring and verification periods, the Project Proponent maintain records of the total sewage/wastewater treated through the STP and the quantity of solid waste/sludge generated and not available for reuse, including the corresponding proportion/percentage, to facilitate accurate determination of the quantity of treated wastewater available for reuse and RoU estimation.
Conclusion	Based on the documents reviewed, site inspection, and verification of the revised year-wise RoU calculations incorporated in the updated PCNMR, including application of the applicable 2% conservative uncertainty deduction, the final eligible RoU quantity for the Project Activity is assessed at 42,89,322 m³.

D.8 PCN+Monitoring Report

Means of Project Verification	For PCNMR assessment below were reviewed: • PCNMR format and contents submitted by the Project Proponent. • Applicability of the UWR Verification Standard and UWR RoU Standard. • Basis and criteria considered for ETP treated water reuse, RO permeate reuse, and STP reuse calculations under Scope 4 & 5. • Supporting operational records, monitoring data, and calculation sheets submitted by the Project Proponent.
Findings	• CL-07 was raised regarding submission of authorization/NOC for availing the RoUs generated through the Project Activity. • CAR-01 was raised as the RoU calculations presented in Table 11.1 were not fully consistent with the source data provided in

	Tables 10.2, 10.3, and 10.4 of the PCNMR. The Project Proponent subsequently submitted an updated PCNMR incorporating the revised year-wise RoU calculations and the applicable 2% conservative uncertainty deduction. The revised calculations were reviewed and found satisfactory, and CAR-01 was subsequently closed.
Conclusion	The updated PCNMR was reviewed and found to be in line with the applicable UWR Verification Standard and UWR RoU Standard, including the revised year-wise RoU calculations and application of the applicable 2% conservative uncertainty deduction. The supporting clarifications and documentation submitted during the verification process were also reviewed and found satisfactory.

D. 9 National Water Security Index

Means of Project Verification	Not applicable.
Findings	-
Conclusion	The National Water Security Index is not considered relevant for RoU estimation of the Project Activity under Scope 4 and Scope 5.

D. 10 Start date, crediting period and duration

Means of Project Verification	Project Documentation: Detailed records and reports, such as the Project Concept Note & Monitoring Report (PCNMR), which outline the project's timeline and milestones. Official Records: Administrative documents, including permits, agreements, approvals and clarifications, confirming the project's initiation and operational phases. Supporting Operational Records: STP/ETP operational records, AMC sewage records, maintenance records and other relevant documentation were reviewed to establish continuity of operation during the claimed crediting period.
Findings	CL-04, CL-05 and CL-06 were raised to obtain and verify supporting information relating to the STP inlet data, ETP commissioning and availability of commissioning records, maintenance records and AMC sewage inlet records relevant to establishing the operational status and continuity of the Project Activity. The information and supporting records provided during verification were reviewed and considered satisfactory for establishing the commencement and continuity of the Project Activity during the claimed crediting period.
Conclusion	Based on the documents reviewed, supporting records and clarifications provided during verification, the project start date, operational continuity and claimed crediting period were found acceptable under the applicable UWR RoU requirements..

D. 11 Positive Environmental impacts

Means of Project Verification	To assess that the Project Activity does not cause any net harm to the environment, a site visit was conducted. Observations of the STP, ETP, and RO systems were carried out, and operational data related to wastewater treatment and reuse was reviewed.
Findings	The STP monitoring data and supporting records reviewed during verification were found to be consistent with the operation of the treatment system.



	- The ETP system was found to be operational and actively treating the effluent generated from the Project Activity. - The reuse of treated wastewater and RO permeate contributes to the conservation of freshwater resources and provides a positive environmental impact. - The Project Activity promotes sustainable water management through the treatment, reuse and recycling of wastewater.
Conclusion	The Project Activity was found to comply with the applicable requirements of the UWR RoU Standard and does not indicate any net negative environmental impact based on the verification findings.

D. 12 Project Owner- Identification and communication

Means of Project Verification	The project owner's identification and communication was verified by below: - Email communication - Phone calls - Site Visits - Supporting certificates and documents submitted by the Project Proponent in relation to the ownership of the land, plant and machinery associated with the Project Activity, as reviewed under CL-07
Findings	Detailed supporting documents were shared by the owner for the verification of PCNMR. Upon verification it was found that the project owner has maintained records and details required and has provided CA certificate as required to prove the ownership has been requested as per CL-07
Conclusion	Based on the CA Certificate and supporting documents reviewed, the plant, machinery and building associated with the Project Activity are under the ownership of the Project Proponent, while the land is owned by Arvind Limited and is being used by the Project Proponent on a lease basis. Accordingly, the ownership and usage arrangements were considered satisfactorily clarified and CL-07 stands closed.

D. 13 Positive Social Impact/Ecological Aspects/Recharge Aspects

Means of Project Verification	Visit was conducted to verify the implementation and operational status of the Project Activity.
Findings	No specific positive social or ecological intervention beyond the reuse of treated wastewater was observed/claimed under this Project Activity. Environment Clearance Report was submitted by PP
Conclusion	The Project Activity contributes indirectly towards environmental sustainability through reduction in freshwater consumption and reuse of treated wastewater, thereby supporting resource conservation.

D.14 Sustainable development aspects

Means of Project Verification	Below mentioned details were required/ checked to review the sustainable development aspects: Site visit: observing the ongoing treatment process, working of the STP, reading of meter were checked
Findings	The STP, ETP, and RO systems were found operational during the site visit and were being used for treatment and reuse of

	wastewater within the facility. • Meter readings and operational data reviewed were found consistent with the reuse and recycling arrangements implemented at site.
Conclusion	Scope 4 & 5 requirements are sufficiently fulfilled, and the Project Activity supports sustainable development through reduction in freshwater consumption and reuse of treated wastewater.

Internal quality control

During the project verification phase, stringent quality control measures were implemented to ensure that all calculations and assessments were accurate, reliable, and transparent. This included detailed audits and reviews of internal documents, reports, and calculations submitted during the verification process in order to identify and rectify any discrepancies or errors.

The verification team underwent continuous training and capacity-building initiatives to ensure that their technical knowledge and skills remained updated in line with current requirements and standards. Clear step-by-step procedures and Standard Operating Procedures (SOPs) were followed for data collection, analysis, and reporting, ensuring that the verification activities were conducted in accordance with UWR Standards.

All records and supporting documents were systematically maintained in an organized and transparent manner, clearly demonstrating the source, methodology, and applicability of the data used. Internal team reviews and technical discussions were carried out to evaluate variations, assess calculation differences, and seek necessary clarifications or revised reports/data wherever required.

Project Verification opinion

Based on the verification activities undertaken, including review of the Project Concept Note and Monitoring Report (PCNMR), supporting documents, water balance and RoU calculation sheets, operational and monitoring records, clarification responses, physical site inspection and reconciliation of the data and calculations, INI Infrastructure & Engineering Private Limited, as the UWR RoU Project Verifier, is of the opinion that the Project Activity titled “**Gainful use of sewage wastewater and industrial effluent at Ankur Textiles Ltd.**” has been implemented and operated in accordance with the applicable requirements of the UWR RoU Standard and the applicable verification requirements for **RoU Scope 4 and Scope 5**.

The Project Activity, comprising treatment and gainful reuse of sewage wastewater and industrial effluent through the STP, ETP and RO systems, was physically verified at the project site. The operational status of the treatment and reuse systems and the monitoring arrangements were found to be consistent with the Project Activity described in the PCNMR. The water data, supporting records and calculation parameters relied upon for RoU estimation were reviewed and found acceptable for verification purposes, subject to the reconciliation undertaken during the verification process.

During verification, an inconsistency was identified between the RoU calculations presented in **Table 11.1** of the PCNMR and the underlying water reuse data provided in **Tables 10.2, 10.3**



and 10.4. Accordingly, **CAR-01** was raised. The Project Proponent subsequently submitted an updated PCNMR incorporating the revised RoU calculations. Based on the revised calculations, the gross RoU quantity was revised from **43,22,486 m³ to 43,76,859 m³**. The applicable **2% conservative uncertainty deduction** was thereafter applied to the respective vintage-year RoU quantities in accordance with the applicable UWR requirements. Following application of the prescribed deduction, the **final eligible RoU quantity for the verification period from 01/01/2015 to 31/12/2025 was determined as 42,89,322 m³**.

The Verifier further assessed the use of treated sewage wastewater sourced from Ahmedabad Municipal Corporation and the corresponding supporting records. The operational functionality of the ETP was also physically verified. Although the ETP commissioning report was not available, the available O&M records, operational monitoring data and physical verification of the system provided sufficient basis for the Verifier to assess the operational status and the data used for RoU estimation as acceptable for the present verification.


The Verifier has also reviewed the authorization provided by Ankur Textiles Ltd. for availing the RoUs generated from the Project Activity by **Arvind Envisol Limited**, supported by the NOC submitted during the verification process.

On the basis of the evidence reviewed and verification activities performed, the Verifier is satisfied that the Project Activity meets the applicable eligibility and applicability requirements under UWR RoU Scope 4 and Scope 5, the RoU estimation is supported by the verified data and reconciliation undertaken, and the Project Activity is not likely to cause any net harm to the environment or society.

Accordingly, INI Infrastructure & Engineering Private Limited is of the opinion that the Project Activity satisfies the applicable UWR requirements and **recommends 42,89,322 m³ of RoUs for consideration for registration under the UWR RoU Program** for the verification period from **01/01/2015 to 31/12/2025**.

Abbreviations

Abbreviations	Full texts
PCNMR	Project Concept Note and Monitoring Report
PP	Project Proponent
CL	Clarification Request
CAR	Corrective Action Request
FAR	Forward Actions Required
PO	Project Owner
UWR	Universal Water Registry
VR	Verification Report
VS	Verification Statement
ROUS	Rainwater Off Set Units
SDGC	Sustainable Development Goals C
STP	Sewage Treatment Plant
ETP	Effluent Treatment Plant
AMC	Ahmedabad Municipal Corporation



Competence of team members and technical reviewers

Sr. No.	Role	Name	Education Qualification	Related experience
1	Team Leader/ Validator	Chintan Thanki	C.A, M. Com	1 Year
2	Technical Reviewer, Approver	Nehal Thakkar	B.Tech, IGBC AP	1 Year
3	Technical review	Vishal Vadukul	B.Tech	-
4	Legal Aspects and Report Generation	Anjali Vellotuparambil	LL.M, LL. B	1 Year

Document reviewed or referenced


No.	Author	Title	Provider
1.	SDGC	PCNMR	SDGC
2.	PP	Calculation Sheet	PP/SDGC
3.	UWR	UWR Standard	UWR
4.	UWR	UWR Verification Standard	UWR
5.	PP	STP Usage Sheet	PP
6.	Krivi Engineers	Water Meter Calibration report	PP
7.	Arvind Envisole Ltd	ETP Maintenance Contract	PP
8.	PP	Occupancy Data	PP
9.	Umiya environmental Solutions	Environment Audit report	PP

Clarifications Request, Corrective Action Request and Forward Action Request

Table 1. CLs from this Project Verification

CL ID	01	Section no.	Date: 03-04-2026
Description of CL			
PP shall provide supporting documents/log sheets detailing the number of employees and working days for each year considered during the assessment period.			
Project Owner's response			Date: 04-05-2026
The Project Proponent submitted the employee records and working-day details for the relevant assessment period.			
Documentation provided by Project Owner			
Occupation data submitted			
UWR Project Verifier assessment			Date: 28-05-2026
The documents submitted by the Project Proponent were reviewed and found satisfactory and consistent with the data and calculations considered in the PCNMR.			

CL ID	02	Section no.	Date: 03-04-2026
Description of CL			
PP shall provide ETP treatment process flow diagram.			
Project Owner's response			Date: 04-05-2026
The Project Proponent submitted the ETP treatment process flow diagram.			
Documentation provided by Project Owner			
ETP treatment process flow diagram			
UWR Project Verifier assessment			Date: 28-05-2026
The process flow diagram submitted by the PP was reviewed and found to be consistent with the actual treatment process and operational system observed during the site verification.			



CL ID	03	Section no.	Date: 03-04-2026
Description of CL			
<i>PP shall provide ETP input water quality and ETP treated output water quality test reports.</i>			
Project Owner's response			Date: 04-05-2026
<i>The Project Proponent submitted the ETP input and treated output water quality test reports.</i>			
Documentation provided by Project Owner			
• ETP inlet water quality test reports • ETP treated water quality test reports			
UWR Project Verifier assessment			Date: 28-05-2026
The submitted test reports were reviewed and found satisfactory and consistent with the water quality parameters and supporting calculations considered in the PCNMR and the applicable UWR requirements.			

CL ID	04	Section no.	Date: 03-04-2026
Description of CL			
<i>PP shall provide ETP commencement/commissioning report from OEM/vendor of the STP/ETP system. PP shall provide ETP maintenance contract details, if any, with the OEM/vendor of the STP/ETP system.</i>			
Project Owner's response			Date: 04-05-2026
<i>The Project Proponent informed that, the commissioning report is not available; however, The Project Proponent submitted the available maintenance and operational records pertaining to the ETP system</i>			
Documentation provided by Project Owner			
• Operation & Maintenance (O&M) records • Operational monitoring records			
UWR Project Verifier assessment			Date: 28-05-2026
Although the ETP commissioning report was not available, the operational status and functionality of the ETP system were physically verified during the site visit. The available O&M records and operational monitoring data submitted by the Project Proponent were reviewed and found acceptable for verification purposes.			

CL ID	05	Section no.	Date: 03-04-2026
Description of CL			
<i>PP shall provide log sheets/data records for municipal sewage inlet sourced from AMC.</i>			
Project Owner's response			Date: 04-05-2026
<i>The Project Proponent submitted the log sheets and supporting records for municipal sewage water received from AMC.</i>			
Documentation provided by Project Owner			
• AMC sewage inlet records/log sheets • Supporting operational records			
UWR Project Verifier assessment			Date: 28-05-2026
The records submitted by the Project Proponent were reviewed and cross-verified with the values considered in Table 10.2 of the PCNMR. The STP inlet quantities were found to be consistent with the data provided and considered acceptable for verification purposes.			

CL ID	06	Section no.	Date: 03-04-2026
Description of CL			
<i>PP shall provide Calibration Certificate of all water meters installed at site</i>			
Project Owner's response			Date: 04-05-2026
<i>submitted the calibration certificates of the installed water meters.</i>			
Documentation provided by Project Owner			
• Water meter calibration certificates • Supporting monitoring records			
UWR Project Verifier assessment			Date: 28-05-2026



The calibration certificates and supporting records submitted by the Project Proponent were reviewed to verify the reliability and accuracy of the meter readings considered in the calculations. The same were found satisfactory and consistent with the data and calculations provided in the PCNMR.

CL ID	07	Section no.		Date: 28-05-2026
Description of CL				
<i>PP shall provide No Objection Certificate (NOC) and CA Certificate for availing the RoUs generated through the project activity by Arvind Envisol Limited.</i>				
Project Owner's response				Date: 27-07-2026
<i>The Project Proponent submitted the required NOC and CA Certificate in support of the authorization for availing the RoUs generated through the Project Activity and the ownership details of the project site, land, plant and machinery respectively..</i>				
Documentation provided by Project Owner				
- NoC - CA Certificate				
UWR Project Verifier assessment				Date: 03/08/2026
The NOC and CA Certificate submitted by the Project Proponent were reviewed. The NOC was found to provide the required authorization for Arvind Envisol Limited to avail the RoUs generated through the Project Activity. The CA Certificate was also reviewed and found consistent with the ownership details and supporting information provided. Accordingly, the clarification was considered satisfactorily addressed.				

Table 2. CARs from this Project Verification

CAR ID	01	Section no.		Date: 03-04-2026
Description of CAR				
The RoU calculations presented in Table 11.1 of the PCNMR were found to be inconsistent with the values and source data provided in Tables 10.2, 10.3 and 10.4. Accordingly, correction and reconciliation of the RoU calculations is required. Further, the applicable 2% conservative uncertainty deduction, in accordance with the UWR RoU Standard, is required to be applied to the revised RoU quantity for determining the net RoU quantity eligible for assignment.				
Project Owner's response				Date: 18-08-2026
<i>The Project Proponent submitted an updated PCNMR incorporating the revised year-wise RoU calculations and the applicable 2% conservative uncertainty deduction.</i>				
Documentation provided by Project Owner				
<i>Updated PCNMR</i>				
UWR Project Verifier assessment				Date: 19-08-2026
The updated PCNMR submitted by the Project Proponent was reviewed. The revised RoU calculations resulted in an increase in the gross RoU quantity from 43,22,486 m³ to 43,76,859 m³. The applicable 2% conservative uncertainty deduction was applied to the respective vintage-year RoU quantities in accordance with the applicable UWR RoU requirements. Accordingly, the revised year-wise calculations resulted in a final eligible RoU quantity of 42,89,322 m³. The revised calculations incorporated in the updated PCNMR were reviewed and found satisfactory. Accordingly, CAR-01 stands closed. Status: Closed – revised year-wise RoU calculations and the applicable 2% conservative uncertainty deduction were incorporated in the updated PCNMR and found satisfactory upon verification.				




Table 3. FARs from this Project Verification

FAR ID	01	Section no.		Date: 03-04-2026
Description of FAR				
<i>PP shall, in future, install and maintain automated meter reading/monitoring systems in place of manual meter readings for operational and monitoring purposes.</i>				
Project Owner's response				Date: 04-05-2026
<i>The Project Proponent agreed to the same and informed that automated meter reading systems shall be considered and implemented in future.</i>				
Documentation provided by Project Owner				
• Existing meter reading records • Monitoring records				
UWR Project Verifier assessment				Date: 28-05-2026
The use of automated meter reading systems would minimize the possibility of manual or human error in monitoring and recording data. However, the manual meter readings and supporting records currently maintained by the Project Proponent were reviewed during verification and found acceptable and consistent with the data and calculations considered in the PCNMR.				

FAR ID	02	Section no.		Date: 20-08-2026
Description of FAR				
<i>The Project Proponent shall, for future monitoring and verification periods, maintain records of the quantity of sewage/wastewater received and treated through the STP and the corresponding quantity of solid waste/sludge generated and disposed of or otherwise not reused. The records should enable determination of the proportion/percentage of the total sewage/wastewater treated that is converted into solid waste/sludge and is not available for reuse.</i>				
Project Owner's response				Date:
-				
Documentation provided by Project Owner				
-				
UWR Project Verifier assessment				Date: 20-08-2026
The Project Proponent does not currently maintain specific records establishing the quantity or proportion of solid waste/sludge generated from the total sewage/wastewater treated through the STP. Accordingly, as a forward action, the Project Proponent is advised to maintain records of the total sewage/wastewater treated, the quantity of solid waste/sludge generated and the corresponding quantity/percentage not available for reuse. Such records will provide a clear basis for determining the actual quantity of treated wastewater available for reuse in future monitoring and verification periods.				

